



SOUTHWEST MIRAMICHI RIVER BRIDGE NO.4

LOCATION: DOAKTOWN, NEW BRUNSWICK



CONSTRUCTION: REHABILITATION AND ENCAPSULATION OF 6 PIER CAPS, WITH THE USE OF 10–150TON AND 5–160TON JACKS THE BRIDGE WAS SYSTEMATICALLY LIFTED TO REPLACE 40 VULKENIZED RUBBER BEARING PADS. ALSO TWO PIER SHAFTS RECEIVED EXTERNAL REINFORCING FRP WRAP DUE TO THEIR CONDITION.



CLIENT: NEW BRUNSWICK DEPARTMENT OF TRASPOTATION AND INFRASTRUCTURE

JOB REFEREANCE: NBDTI CONTRACT # 15-0468



DATE: BEGAN MAY 2015,
COMPLETED OCT 2016

UNIQUENESS: ACCESSING BRIDGE PIERS WITH BARGES AND HANGING ENGINEERED PLATFORMS, LIFTING THE BRIDGE WITH 15, 150 AND 160TON JACKS, EXTRANAL REINFORCING, FIBER REINFORCED POLYMER WRAP.

ATLANTIC UNDERGROUND SERVICES LTD.

425 PINE GLEN RD • RIVERVIEW, N.B. • E1B 4J8 • (506)387-8160

INFO@AUSLTD.COM